

Road Name: Keslinger Road (from South First Street to IL Route 23)
Minnegan Road (from Anderland Road to South First Street)

Road District: Afton

Location: See above

Anticipated Start Date: July 10, 2019

Completion Date: July 11, 2019

Contractor: Steffens 3-D Construction

Estimated Cost: \$88,848.43

Improvements: For Minnegan - Single Seal - Placement of bituminous material (oil) Seal, HFE-150 at a rate of .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift
For Keslinger -Double Seal - Placement of bituminous material (oil) Prime , MC-30 Seal, at a rate of .30 gallons per square yard; 1st Lift of Seal HFE-150 at .40 gallons per square yard; second lift of seal HFE-150 at .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift

Traffic: If contractor elects to seal entire road at once, and if approved by the County Engineer, road may be closed to through traffic on a rolling closure basis.