

Road Name: Glidden Road (from Cherry Valley Road to Herbert Road)  
Wolf Road (from Myelle Road to Glidden Road)

Road District: Kingston

Location: See above

Anticipated Start Date: Wolf Road, July 1, 2019; Glidden Road, July 2, 2019

**Estimated Completion Date: July 3, 2019**

Contractor: Steffens 3-D Construction

**Estimated Cost: \$31,093.77**

Improvements: For Single Seal - Placement of bituminous material (oil) Seal, HFE-150 at a rate of .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift

Traffic: If contractor elects to seal entire road at once, and if approved by the County Engineer, road may be closed to through traffic on a rolling closure basis.