

Road Name: Aldrich Road (from Ault Road to Glidden Road)  
Johnson Road (from Old State Road Aldrich Road)  
Pleasant Hill Road (from North Grove Road to Baseline Road)  
Base Line Road (Five Points Road to Township Line)  
Aldrich Road (from Pleasant Hill Road to west edge of bridge deck)

Road District: Mayfield

Location: See above

Anticipated Start Date: Base Line Road 7/2/2019; Remaining Roads 7/8/2019

**Estimated Completion Date: July 9, 2019**

Contractor: Steffens 3-D Construction

**Estimated Cost: \$139,139.05**

Improvements: For Single Seal - Placement of bituminous material (oil) Seal, HFE-150 at a rate of .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift. For Aldrich Road (Pleasant Hill Road to bridge deck) -Double Seal - Placement of bituminous material (oil) Prime , MC-30 Seal, at a rate of .30 gallons per square yard; 1<sup>st</sup> Lift of Seal HFE-150 at .40 gallons per square yard; second lift of seal HFE-150 at .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift

Traffic: If contractor elects to seal entire road at once, and if approved by the County Engineer, road may be closed to through traffic on a rolling closure basis.