

Road Name: Houghtby Road (from Shabbona Road west to bridge)
Road District: Shabbona
Location: See above
Anticipated Start Date: July 12, 2019
Estimated Completion Date: July 13, 2019
Contractor: Steffens 3-D Construction
Estimated Cost: \$22,879.55
Improvements: Double Seal - Placement of bituminous material (oil) Prime , MC-30 Seal, at a rate of .30 gallons per square yard; 1st Lift of Seal HFE-150 at .40 gallons per square yard; second lift of seal HFE-150 at .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift

Traffic: If contractor elects to seal entire road at once, and if approved by the County Engineer, road may be closed to through traffic on a rolling closure basis.