

Street Name: Governor Beveridge Highway (from North Street to Village Limits)
Municipality: Village of Somonauk
Location: See above
Anticipated Start Date: July 15, 2019
Estimated Completion Date: July 16, 2019
Contractor: Steffens 3-D Construction
Estimated Cost: \$13,073.42
Improvements: For - Single Seal - Placement of bituminous material
(oil) Seal, HFE-150 at a rate of .40 gallons per square yard and seal coat
aggregate placed at a rate of 24 pounds per square yard per lift

Traffic: If contractor elects to seal entire road at once, and if approved by
the County Engineer, road may be closed to through traffic on a rolling
closure basis.