

Road Name: Mowers Road (Malta Road west for 455 feet)  
West Clair Road (Clare Road west for 1,245 feet)  
Schafer Road (from Il Route 64 north for 1.280 feet)  
McQueen Road (from 1065 feet north of IL Rt 64 to 1600 south of IL Rt 64)

Road District: South Grove

Location: See above

Anticipated Start Date: July 8, 2019

**Estimated Completion Date: July 9, 2019**

Contractor: Steffens 3-D Construction

**Estimated Cost: \$41,486.65**

Improvements: Double Seal - Placement of bituminous material (oil) Prime, MC-30 Seal, at a rate of .30 gallons per square yard; 1<sup>st</sup> Lift of Seal HFE-150 at .40 gallons per square yard; second lift of seal HFE-150 at .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift

Traffic: If contractor elects to seal entire road at once, and if approved by the County Engineer, road may be closed to through traffic on a rolling closure basis.