

Road Name: Lloyd Road (from Il Rt 23 to Base Line Road)  
Story Road (from Lloyd Road to Moose Range Road)  
Moose Range Road (from Whipple Road to Base Line Road)  
County Line Road (from Plank Road to Buzzell Road)

Road District: Sycamore

Location: See above

Anticipated Start Date: July 5, 2019

**Estimated Completion Date: July 6, 2019**

Contractor: Steffens 3-D Construction

**Estimated Cost: \$173,329.82**

Improvements: Double Seal – (Lloyd, Story and County Line Roads) - Placement of bituminous material (oil) Prime, MC-30 Seal, at a rate of .30 gallons per square yard; 1<sup>st</sup> Lift of Seal HFE-150 at .40 gallons per square yard; second lift of seal HFE-150 at .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift  
For Moose Range Road - Single Seal - Placement of bituminous material (oil) Seal, HFE-150 at a rate of .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift

Traffic: If contractor elects to seal entire road at once, and if approved by the County Engineer, road may be closed to through traffic on a rolling closure basis.