

Road Name: Hinckley Road (Perry Road to Keslinger Road)
McGirr Road (Somonauk Road to Hinckley Road)
McGirr Road (Pritchard Road to County Line Road)

Road District: Pierce

Anticipated Start Date: Not prior to June 15, 2020

Completion Date: Project has a completion date of July 31, 2020.

Contractor: Steffens 3-D Construction

Estimated Cost: \$60,999.00

Improvements: Single Seal - Placement of bituminous material (oil) Seal, HFE-150 at a rate of .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift

Traffic: If contractor elects to seal entire road at once, and if approved by the County Engineer, road may be closed to through traffic on a rolling closure basis.