

Road Name: Lukens Road (Plank Road to east of Darnell Road)
Buzzell Road (Lukins Road to East County Line Road)
East County Line Road (North of Plank Road to Buzzell Road)
Corson Drive (Kishwaukee Drive to Base Line Road) **Double Seal**

Road District: Sycamore

Anticipated Start Date: Not prior to June 15, 2020

Completion Date: Project has a completion date of July 31, 2020.

Contractor: Steffens 3-D Construction

Estimated Cost: \$58,837.56

Improvements: Single Seal - Placement of bituminous material (oil) Seal, HFE-150 at a rate of .40 gallons per square yard and seal coat aggregate placed at a rate of 24 pounds per square yard per lift; Double Seal on Corson Drive

Traffic: If contractor elects to seal entire road at once, and if approved by the County Engineer, road may be closed to through traffic on a rolling closure basis.